

University of Memphis

University of Memphis Digital Commons

TDOT Standard Specifications

Department of Transportation

12-15-2021

Supplemental Specifications (100SS) of the Standard Specifications for Road and Bridge Construction, January 1, 2021

Tennessee. Department of Transportation.

Follow this and additional works at: <https://digitalcommons.memphis.edu/govpubs-tn-dept-transportation-standard-specifications>

Recommended Citation

Tennessee. Department of Transportation., "Supplemental Specifications (100SS) of the Standard Specifications for Road and Bridge Construction, January 1, 2021" (2021). *TDOT Standard Specifications*. 2.

<https://digitalcommons.memphis.edu/govpubs-tn-dept-transportation-standard-specifications/2>

This Report is brought to you for free and open access by the Department of Transportation at University of Memphis Digital Commons. It has been accepted for inclusion in TDOT Standard Specifications by an authorized administrator of University of Memphis Digital Commons. For more information, please contact khggerty@memphis.edu.

STATE

(Rev. 9-7-21)

(Rev. 12-15-21)

OF

TENNESSEE

January 1, 2021

Supplemental Specifications – 100SS

of the

Standard Specifications for Road and Bridge Construction

January 1, 2021

Subsection 104.03.B & C (pg. 23-24), 9-7-21; **Contract Change Notification; B & C**; Revise subsections:

B. Written Acknowledgement by Engineer

The Engineer will provide written acknowledgement of the Contractor's written notice within ten (10) calendar days.

C. Written Response by Engineer

The Engineer will provide a written response within the specified number of calendar days based on the requested contract change:

1. For requested changes to the contract time in excess of one hundred eighty (180) days or requested changes that alter the original contract amount by more than \$200,000, the Engineer will respond within thirty (30) days of receiving the Contractor's written notice.
2. For requested changes to the contract time in excess of ninety (90) days but less than or equal to one hundred eighty (180) days, or requested changes that alter the original contract amount by more than \$100,000 but less than or equal to \$200,000, or by more than ten percent (10%) of the original contract, whichever is less, the Engineer will respond within twenty-one (21) days of receiving the Contractor's written notice.
3. For all other requested changes to the contract, the Engineer will respond within fourteen (14) calendar days of receiving the Contractor's written notice.

The written response to the Contractor’s written notice will include one of the following:

1. Confirmation that a change is necessary in accordance with **104.02**, and direction on how the Work will proceed.
2. A denial of the request for a change, which will include references to the Contract as to why the condition does not represent a change.
3. A request for additional information stating the specific information needed and the date by which it must be received. The Engineer will respond to the additional information provided within fourteen (14) calendar days.

When a change is necessary, the Engineer will make appropriate adjustments to the Contract price and time, if warranted, in accordance with **108.07**, **109.04**, **109.05.A**, and **109.06**. If the Contractor disagrees with the Engineer’s decision or does not agree with the Contract adjustments, the Contractor may pursue the issue as a claim in accordance with **105.16**.

Subsection 106.06.A.1 (pg. 61), 12-15-21; **Field Laboratory, Type A**; Revise No. 1:

1. Scales of appropriate capacity and design to weigh the required samples. Scales are to be sensitive to within 0.1% of the sample to be weighed. Provide standard weights for scale calibration. Scale calibration shall ~~be~~ completed annually every six months, by an independent source ~~with no calibration exceeding 6 months to the day in~~.

Subsection 108.01 (pg. 79, 80), 12-15-21; **Subletting of Contract**; Revise Item list:

- Item 105-01 – Construction Stakes, Lines and Grades
- Item 202-01.~~02~~ – Removal of Asbestos
- Item 203-40 – Rock Anchors, Anchor Blocks, Tie Back Anchors
- Item 209 – ~~Project~~ EPSC
- Item 411-12 – ~~** Shoulder~~ Scoring
- Item 411-33 – Stamped Asphalt
- Item 501-03.~~12~~ – Concrete Shoulder Rumble Strip
- Item 503-01 – Grinding Concrete Pavement
- Item 602-03 – Steel Structures
- Item 602-04 – Steel Structures
- ~~Item 602-10.13 / .14 – Navigational Lighting~~
- Item 602-10.81 – Heat Straightening
- Item 603-02 – Repainting Steel Structures
- Item 603-05 – Containment and Disposal of Waste
- Item 604-04.01 – Applied Texture Finish (New Structures),
- Item 604-04.02 – Applied Texture Finish (Existing Structures)
- Item 604-04.10 – Graffiti Protection
- Item 604-04.20&.21 – Painting or Staining Concrete Surfaces
- Item 604-04.62 – Clean and Texture Finish Median Barrier
- Item 604-05.31 – Bridge Deck Grooving (Mechanical)

- Item 604.07 – Retaining Wall
- Item 604-42.01 – Underwater Divers
- Item 606-26.05 – Core Drilling for Piles (Abandoned)
- Item 617 – Bridge Deck Sealant
- Item 619 – Polymer Modified Concrete Overlay
- Item 624 – Retaining Wall ~~Items~~
- Item 625-01.08,10,11 – Inclinator, Camera Drilled Shaft Inspections
- ~~Item 640 – Weigh Station Items~~
- Item 705 – Guardrail, ~~Anchors, etc.~~
- Item 706 – Guardrail Adjusted, Removed and Reset~~Items~~
- Item 707 – Fence ing ~~Items~~
- Item 712 – Temporary Traffic Control ~~Items~~
- Item 713 – Highway Signing ~~Items~~
- Item 714 – Roadway and Structure Lighting ~~Items~~
- Item 716 – Pavement Markings ~~Items~~
- ~~Item 720-03, 720-04, 720-05, 720-06, 720-07, 720-08, 720-09 – Railroad Highway Crossing~~
- ~~Item 721-01.06 – Irrigation System Repair~~
- Item 721-10, 721-11.20, 721-11.30, 721-12 – Landscape and Irrigation
- Item 724 – Landscape Lighting
- Item 725 – ITS items
- Item 730 – Traffic Signals ~~Items~~
- Item 740 – Geosynthetics
- Item 79* – Utilities ~~Items~~
- ~~Item 750.01 – Mitigation Site~~
- Item 801 – Seeding
- Item 802 – Landscaping ~~Items~~ Plantings
- Item 803-01 – Sodding
- Item 805 – Erosion Control
- Item 806 – Project Mowing

Subsection 108.03.A, B, & C (pg. 81,82,85,87,88), 9-7-21; **Contract Change Notification; A & B;** Revise Heading,
C.1.c; Add new No.vi, **C.3;** Revise last paragraph, **C.4;** Revise last paragraph & add sentence:

A. Project Durations Less Than 9 Months

B. Project Durations 9 Months to 24 Months

C.1.c Narrative report in PDF file format fit to 8.5x11 inch paper and including:...

- vi. The quantity and estimated daily production rate for controlling activities;
- vii. Description of the calendars including identification of workdays per week, holidays, number of shifts per day, and number of hours per shift;
- viii. Description of how the schedule accommodates adverse weather days for each month; and

- ix. Description of execution plan, including number and type of crews, a list of subcontractors’ crews, and expected equipment, but not limited to large equipment transport and delivery, transportation permits for oversized/overweight loads, and availability.

3. Baseline CPM Schedule.

The Engineer and Contractor will review the draft baseline CPM schedule at a meeting specific for the review of the schedule. The Engineer will accept the draft baseline CPM schedule, provide review comments, or request additional information. Make appropriate adjustments or provide additional information within 14 calendar days. The Engineer’s acceptance is based solely on whether the baseline schedule meets the requirements of **108.03**. Review comments made by the Engineer on the initial schedule will not relieve the Contractor from compliance with the Contract. The Contractor is responsible for scheduling, sequencing, and prosecuting the Work to comply with the Contract requirements.

4. Schedule Updates.

Submit the updated schedule electronically to the Engineer in accordance with the requirements of this subsection. The Engineer reserves the right to reject any schedule updates because of changes in relationships between activities on the critical path, inadequate or inaccurate narrative updates, or other deficiencies in the schedule updates as required in this subsection.

The Department will measure and pay for CPM Project Schedule in accordance with **108.11** and **108.12** respectively.

Subsection 108.11 (pg. 99), 9-7-21; **Method of Measurement**; Add subsection **108.11**:

108.11 Method of Measurement

The Department will measure construction CPM Project Schedule as a percentage of the lump sum price bid for the completion of the work specified in **108.03.C** and partial payment will be made according to the schedule in Table 108.11-1.

Table 108.11-1: Payment Schedule for CPM Project Schedule

Estimate Number or Percent of Total Contract Amount of Previous Estimate	Total Percent of CPM Project Schedule Lump Sum Bid Item
Estimate # 1	20%
Estimate # 3	40%
20%	50%
40%	60%
60%	70%
80%	80%
95%	100%

Subsection 108.12 (pg. 99), 9-7-21; **Method of Measurement**; Add subsection **108.12**:

108.12 Basis of Payment

The Department will make partial payments for CPM Project Schedule on the basis of a percentage of the lump sum price bid in accordance with the schedule shown in Table 108.11-1.

If the Contractor fails to provide monthly schedule updates, or address the Engineer's comments regarding the monthly schedule update, within 10 calendar days following the progress estimate pay period cutoff date, the Engineer will withhold payment for CPM Project Schedule and may withhold up to an additional 5% of the monthly estimate payment, until such time as an acceptable update has been provided.

No additional payments will be made for schedule revisions as requested per **108.03.D**.

Such payment is full compensation for meeting all requirements of **108.03.C** and **D**.